Augemenation of Bijapur Water Supply Scheme from Krishna River.

Group I. Pipe Line Works.

A. Laying and jointing raw water rising main of 450 mm (18") Dia. C.I. Pipe of 14,580 RM (47,800 Rft) from Baluti Head Works to purification works at Malghan. Rs. 2,67,840.

B. Laying and jointing pure water rising main consisting of 400 mm (16") C.I. Pipe of Length of 8310 Rm (28,000 Rft) from Purification works to break pressure tank near Mulawad Rs. 1,55,930.

C. Laying and jointing gravity main consisting of 400 mm (16") Dia. C.I. Pipe of 10,650 RM (35,000 Rft) length and 450 mm (18") Dia. C.I. Pipe of length 17.070 RM. (56,000 Rft) from Break Pressure tank near Mulawad to Bijapur Rs. 5,13,607.

D. Providing laying and jointing feeder main of 525 mm (21", Dia. R.C.C. P2 class of pipe of length 1050 RM. (3,400 Rft) from proposed Service Reservior at Sainik School to the existing service Reservior. Rs. 75,480.

E. Constructing service Road along pure water rising main from Malghan to Mulawad village and near Begaum Tank etc., and improvements to existing cart track from Baluti to Asangi including construction of cross drainage works from Baluti to Mulawad. Rs. 1,48,620.

F. Constructing of Break Pressure Tank. Rs. 12,133.

Total Group I.
11,73,610.
29,340.
18 months.
Item Rate.
Rs. 50.
Class I only.

Group II. Treatment Works:

A. Providing purification works 5.0 M Litres per day (1.10 mgd) capacity near Malghan village comprising of chemical house aeration fountaxion flash mixer, floculator clarifier and filter house and mechanical equipment for the same Rs. 3,41,340.

B. Construction of pure water sump and pump house. Rs. 1,28,332.

C. Providing improvements to existing Bhutnal Water Works *viz.*, providing 450 mm (18") dia. outlet pipe and purification works comprising of chemical house wash water tank, and modifications to slow sand filters and converting it into settling tank and filter house etc., with necessary mechanical equipment for the same and pure water tank 13.62 lacs liters (3.00 Lakh Glns.) capacity and additional sump well etc., Rs 4,22,851.

Total Group II.
8,93,023.
22,326.
18 months.
Lump Sums.
Rs. 40.
Class II and above.

Group III. Pumping Machinery

A. Providing and erecting raw water electrically drive deep well turbine pump sets at existing hea works at Baluti lift irrigation scheme. Rs. 1,83,50

B. Providing and erecting pure water electrically drive centrifugal pump sets at purification works nea Malghan village. Rs 1,32,500.

Total Group III.
3,16,000.
7,900.
12 months.
Item Rate.
Rs. 25.
Class II and above.

Group IV. Quarters and Reservoir:

A. Construction of Staff Quarters at Head Works nea Baluti and purification works near Malghan villa and at Service reservoir in Bijapur. Rs. 3,05 8

B. Providing barbed wire fencing around quarters a head works near Baluti and purification wor near Malghan and at service reservoir at Bijap and internal roads etc., Rs. 38,536.

C. Constructing ground masonary reservoir of 5.45 Litres (1.20 mgd.) capacity at Saink Schoo Bijapur Rs. 3,19,319

Total Group IV.
6,63,371.
16,590.
18 Months.
Item Rate.
Rs. 25.
Class II and above.

S. B. POLIS GOWDAR,
1179 *Executive Engineer.*

OFFICE OF THE CHIEF ENGINEER, HYDR ELECTRIC CONSTRUCTION PROJECTS, PO BAG No. 360, BANGALORE-9.

Notification dated 16th August 1969.

Tender Notice.

Sub.— Enquiry No. HCP/TLC-26/August 1969 for t supply of 11 kV and 33 kV single core 1,0 sq.mm. aluminium P.I.L.C. cables for Receivi Stations.

No. 17102-15. Sealed tenders in Triplicate will received by the Chief Engineer, Hydro-Electric Constr tion Projects, Race Course Cross Road, Post Bag No. 3 Bangalore-9, upto 3 P.M. on 4th October 1969 fr intending tenderers for the supply of single core 11 and 33, kV., 1,000 sq. mm. aluminium paper insulated le sheathed cable for Shimoga, Hubli, Bangalore a Mangalore receiving stations. The equipment will purchased from the indigenous manufacturers only.

Intending tenderers may on written application to t Chief Engineer, Hydro-Electric Construction Projec Bangalore-9, obtain the requisite tenders should be su

mitted. These tender forms will be available for sale in the office of the undersigned during working hours, from 28th August 1969 and the last day for the sale of the same is 2 P.M. on 3rd October 1969. Application for tender forms shall accompany by a cash remittance of Rs. 40 (Rupees forty only). which is the price fixed for a set of four tender forms. which is not refundable. If the tender forms are to be sent by post to any place in India, an additional sum of Rs. 5 per set to cover the packing and postage charges should be sent along with the cost of tender forms, failing which the tender forms will not be sent and the money will not be accepted.

Cheques and Postage Stamps will not be accepted to words the cost of tender forms nor will the forms be sent by V.P.P. The department will not accept any responsibility for delay in receipt or non receipt of tender forms sent by post.

Telegraphic quotations and quotations not accompanied by "Earnest Money" will not be accepted.

Tenders received will be opened at 4 P.M. on 4th October 1969 in the presence of such of these tenderers who may choose to be present.

1242 B. SHANKARAPPA, *Chief Engineer.*

OFFICE OF THE EXECUTIVE ENGINEER, P.W.D., YADGIR DIVISION YADGRI.

Brief Tender Notification.

Subject to the conditions stipulated in the detailed Notification in this behalf, item rate tenders in duplicate in sealed covers duly signed by the tenderers superscribed with the name of works are invited from the registered contractors of appropriate Classes of Mysore Public Works Department and will be received by Executive Engineer, P.W.D. Yadgir Division up to 4-00 P.M. on 18th September 1969 for the following works.

Tenders will be opened if possible in the presence of Contractors or their authorised agents. Blank tender forms can be had from Office of the Executive Engineer P W.D., Yadgir Division on any working days during working hours, from 16th September 1969 to 17th September 1969 on the payment as noted in column No. 5 (Not refundable).

The requisition for purchasing tender Schedule should reach this office on or before 12th September 1969.

Note.—(i) The competent-authority to accept the tender, reserves the right to reject any or all the tenders without assigning any reasons.

(ii) Further particulars can be had from the office of the Executive Engineer, P.W.D., Yadgir Division, on any working days during office hours.

Sl. No.	Name of work	Estimated cost of work Put to Tender	E.M.D. 2½%	Cost of tender Schedule *Plus* Sales Tax.	Period for completion of work exclud-ing rainy Season	Class of Contractor
1	2	3	4	5	6	7
		Rs.		Rs.		
1	Improvements to Chigarhalli-Malli Road Taluk : Jewargi District Gulbarga (II coll).	4,50,000	11,250	30—60	18 Months	II and above.
2	Constn : of P. H. Centre Building at Kakkera Taluk : Shorapur District : Gulbarga.	1,24,700	3108	30—60	12 Months	III and above.
3	Construction of Building Primary Health centre at Yedrami Taluk : Jewargi District : Gulbarga.	99,300	2,483	10—20	10 Months	III and above.

1241 M. S. MURTHY,
For *Executive Engineer.*